



ADDENDUM #1 INFORMAL BID 2017-134

KITSAP COUNTY FACILITIES MAINTENANCE KITSAP COUNTY YOUTH CENTER MASONRY REPAIR

TO: All Respondents
FROM: Colby Wattling, Buyer
CLOSING DATE: **JUNE 28, 2017 at 3:00PM (CHANGED)**
REF NO.: 2017-134 INFORMAL BID
DATE: June 19, 2017

Please see updated scope of work below

A. Areas to be refurbished include:

1. Administration Building Upper Masonry Caps totaling approximately 16 lineal feet
2. Detention Building Upper Masonry Caps totaling approximately 188 lineal feet
3. Detention Building Lower Masonry Caps totaling approximately 573 lineal feet
4. All measurements to be confirmed by vendor

B. Remove loose surface material on existing upper and lower masonry caps. Be sure to leave drip edging intact as much as possible. Apply a coat of CrownSaver by ChimneySaver (or equivalent) per manufacturer's recommended system to seal and bind remaining masonry cap material.

C. On Upper masonry cap areas install 24 gauge metal flashing over sealed masonry cap and secure as per manufacturer's recommended standards. Flashing color to match existing metal walls.

D. On lower masonry cap areas loosen existing metal wall units to allow tucking the metal flashing up behind and cover the exposed sealed masonry cap. Install 24 gauge metal flashing. Color to match existing metal walls. Once the flashing is installed secure the metal wall units and flashing as per manufacturer's recommended standards.

There are no other changes to the original specifications other than what is changed by Addendum 1.
Acknowledgement of receipt of this and all ADDENDA are required
END OF ADDENDUM #1